City of Clarkson Valley Office Remodel

General Notes / Clarification Sheet

CODE DATA BLOCK

Construction Classification Type	2A
Automatic Fire Suppression System	Yes
Automatic Fire Alarm System	Yes
Corridor Rating	0 Hour
Occupancy Group	В
Project Area	900 SF
High Rise Building	No
# Exits Required / Provided	2/3

Project Description

Installation of 2 interior doors. Installation of Level 3 bullet resistant wall and Level 3 bullet resistant glass transaction window / counter. New carpet and wall paint throughout. Repaint public corridor wall where door was added; one side only to match existing. Reconfigure existing furniture layout per plans. No change to fire suppression system, fire alarm system, ceiling membrane, means of egress or mechanical system. Building standard doors, frames and new recessed light fixture are available in the basement area at no cost to the contractor.

Contact Information

- **Building Owner Representative**
 - Lauren McLaughlin, Operations Project manager
 - Cell : 217-242-5588
 - Email : laurenmclaughlin@eyecarepartners.com _
- City of Clarkson Valley Representative
 - Sue McNamara, Clarkson Valley Mayor
 - 636-227-8607 or 314-541-6022 Office:
 - Email: sue@clarksonvalley.org _

•	current Fire Protection District Building Code as adopted. All construction shall meet the current mechanical, electrical and plumbing codes current Fire blocking shall be required in all concealed spaces where combustible materials are p Fire Protection District may require additional alarm devices and/or fire extinguishers as Bullet resistant construction (walls and glazing and transaction window) shall meet the Le All work shall be completed in a workmanlike manner to the satisfaction of the Clarkson T District Fire Marshal. Sequence of field inspections shall be St. Louis County first, Fire District second and City t All finish materials shall be of commercial quality and installed in accordance with the ma See note on floor plan for coordination with IT / Electrical contractor.
	Contractor Responsibilities
•	Lien waivers for all materials / labor used on this project will be provided to the City of Cl
•	warranty all installations for 6 months following project completion. Contractor shall obtain and abide by a written copy of the <u>building owner rules and regu</u> l
•	include: material storage, working hours, smoking, foul language, noise and behavior of v
•	
•	
	plans dated 8/13/2024. All materials are to be installed in accordance with the material
•	Contractor will notify Clarkson Valley one week ahead of when they anticipate needing the
	new public lobby complete, secure and clean: ready for electronics storage. Clarkson Va
	disassemble and relocate that work. Same concept for re-assembly. See Phasing Note
•	Project Start Date <u>see contract</u> Project Completion Date All change orders are to be in writing and approved, by the City of Clarkson Valley and
•	Means of egress corridors shall never be blocked or compromised in any way and all wor
•	Phasing: New public lobby area to be completed and finished first so it can be used for el
	finishes and furniture set up to be completed after the new public lobby space is occupia
•	Prior to the start of any work the contractor shall provide the City of Clarkson Valley copi compensation insurance documents which also name the City of Clarkson Valley as addit

Contractor to provide wall paint color and floor carpet samples (see notes on plans) prior to ordering those materials. Existing building carpet attic stock may be available for corridor floor patching needs at new door.



y the City of Clarkson Valley, Missouri and shall meet the

ntly adopted by St. Louis County, Missouri.

present.

Construction Notes

needed.

evel 3 standard of the UL752 standard.

Valley Building Commissioner and Fire Protection

third (last). anufacturer's instructions.

alled by the General Contractor.

Valley and installed by the IT / Electrical contractor.

larkson Valley prior to final payment. Contractor shall

lations for operating within and around the building. To workmen.

aces used for material transport or storage as needed.

and to complete the project in accordance with the manufacturer installation instructions.

he office electronics disassembled and will have the alley will then arrange, with IT / Electrical contractor to below.

see contract

Contractor prior to enactment.

rk areas are to secure and safe.

lectronics storage / staging. New door installation,

able and electronics have been moved.

ies of their general liability and workmen's

tional insured.